



400 Richardson Road, Orangeville, Ontario L9W 4W8  
Ph: 519-941-2401 Fax: 519-941-8462 Toll Free: 1-800-637-5910

## **2016 Radiant In-Floor Heating**

\$1.50/Sq. ft. for supply and installation of ½” PEX pipe @ 12” o/c, assumes floor is leveled, thermal insulation is in place and 6” wire mesh grid is in place. Price includes pressure test and pressurization of tubing during concrete pour.

Purging of each loop, pump, water temperature control, thermostat, cushion tank and connection to heat source with isolation, labour and set up

### No Zoning

Up to 750 sq. ft. (3 loops)	\$1,906.31
Up to 1000 sq. ft. (4 loops)	\$1,945.95
Up to 1250 sq. ft. (5 loops)	\$1,985.59
Up to 1500 sq. ft. (6 loops)	\$2,025.23
Up to 1750 sq. ft. (7 loops)	\$2,064.87
Up to 2000 sq. ft. (8 loops)	\$2,104.51
Up to 2250 sq. ft. (9 loops)	\$2,144.15
Up to 2500 sq. ft (10 loops)	\$2,183.79
Up to 2750 sq. ft (11 loops)	\$2,223.43
Up to 3000 sq ft (12 loops)	\$2,263.07

This price is for a closed loop system which requires a boiler or CombiCore water heater (provides separated domestic and potable water). Current plumbing codes preclude the use of potable water in the floor. Closer pipe spacing will increase the price.

Prices include labour and one year labour warranty in addition to any manufacturers parts warranty. Prices may vary depending on the actual installation conditions. Call for a written quotation at no cost or obligation. HST is extra @ 13%.