



"Delivering Care Everyday Since 1924"

400 Richardson Road, Orangeville, Ontario L9W 4W8
 Ph: 519-941-2401 Fax: 519-941-8462 Toll Free: 1-800-637-5910

2019 Radiant In-Floor Heating

\$1.50/Sq. ft. for supply and installation of ½" PEX pipe @ 12" o/c, assumes floor is leveled, thermal insulation is in place and 6" wire mesh grid is in place. Price includes pressure test and pressurization of tubing during concrete pour.

Purging of each loop, pump, water temperature control, thermostat, cushion tank and connection to heat source with isolation, labour and set up

	Copper Manifold No Zoning	Rehau Pro- Balance No Zoning
Up to 750 sq. ft. (3 loops)	\$1,660	\$1,723
Up to 1000 sq. ft. (4 loops)	\$1,715	\$1,790
Up to 1250 sq. ft. (5 loops)	\$1,770	\$1,864
Up to 1500 sq. ft. (6 loops)	\$1,824	\$1,946
Up to 1750 sq. ft. (7 loops)	\$1,879	\$2,013
Up to 2000 sq. ft. (8 loops)	\$1,934	\$2,073
Up to 2250 sq. ft. (9 loops)	\$1,989	\$2,162
Up to 2500 sq. ft (10 loops)	\$2,044	\$2,214
Up to 2750 sq. ft (11 loops)	\$2,099	\$2,288
Up to 3000 sq ft (12 loops)	\$2,154	\$2,363

This price is for a closed loop system which requires a boiler or CombiCore water heater (provides separated domestic and potable water). Current plumbing codes preclude the use of potable water in the floor. Closer pipe spacing will increase the price.

50/50 Glycol mix per 100ft of 1/2" Pex pipe \$35

Prices include labour and one year labour warranty in addition to any manufacturers parts warranty. Prices may vary depending on the actual installation conditions. Call for a written quotation at no cost or obligation. HST is extra @ 13%.