



*"Delivering Care Everyday Since 1924"*

400 Richardson Road, Orangeville, Ontario L9W 4W8  
Ph: 519-941-2401 Fax: 519-941-8462 Toll Free: 1-800-637-5910

## **2024 Radiant In-Floor Heating**

\$1.85/Sq. ft. for supply and installation of ½" PEX pipe per linear foot, assumes floor is leveled, thermal insulation is in place and 6" wire mesh grid is in place. Price includes pressure test and pressurization of tubing during concrete pour.

Fast Form HydroFoam installation including 1/2" pipe.	\$5.00/sqft
Rauboard installation including 10mm pipe.	\$27.00/sqft

Purging of each loop, pump, water temperature control, thermostat, cushion tank and connection to heat source with isolation, labour and set up

	Rehau Pro-Balance No Zoning
3 Loop manifold	\$2,564
4 Loop manifold	\$2,631
5 Loop manifold	\$2,708
6 Loop manifold	\$2,792
7 Loop manifold	\$2,861
8 Loop manifold	\$2,922
9 Loop manifold	\$3,012
10 Loop manifold	\$3,066
11 Loop manifold	\$3,142
12 Loop manifold	\$3,218

This price is for a closed loop system which requires a boiler or CombiCore water heater (provides separated domestic and potable water). Current plumbing codes preclude the use of potable water in the floor.

50/50 Glycol mix per 100ft of 1/2" Pex pipe	\$55
---	------

Prices include labour and one year labour warranty in addition to any manufacturers parts warranty. Prices may vary depending on the actual installation conditions. Call for a written quotation at no cost or obligation. HST is extra @ 13%.